iJRASET
International Journal For Research in Applied Science and Engineering Technology



INTERNATIONAL JOURNAL FOR RESEARCH

IN APPLIED SCIENCE & ENGINEERING TECHNOLOGY

Volume: 14 **Issue:** XI **Month of publication:** November 2026

DOI: https://doi.org/10.22214/ijraset.2026.85671

www.ijraset.com

Call: 08813907089 | E-mail ID: ijraset@gmail.com

International Journal for Research in Applied Science & Engineering Technology (IJRASET)
ISSN: 2321-9653; IC Value: 45.98; SJ Impact Factor: 7.538
Volume 14 Issue XI Nov 2026- Available at www.ijraset.com

Automatic Dam Operating System: A Sensor-Based Approach to Reservoir Monitoring and Gate Control

Nihal Haris[1], Sreya KT[2], Arya M[3], Raseesul Haque[4]
[#]*Department of Civil Engineering, Eranad Knowledge City Technical Campus, Manjeri, Malappuram, Kerala, India*

Abstract: ***Dams serve irrigation, drinking water, hydropower and flood moderation, yet gate handling at many sites still leans on people watching gauges and passing instructions along. When a reservoir rises fast during intense rain, even a short delay can matter. This paper presents the concept and the Phase I study of an Automatic Dam Operating System in which water-level sensors feed a microcontroller that compares readings against preset limits and commands a motor-driven gate, while alarms and an IoT link keep operators informed. Four recent studies on AI-based prediction, threshold control, servo-driven shutters and IoT monitoring are reviewed and compared, and the gap they leave is identified. A ten-stage methodology, running from site selection at Kanjirampuzha Dam, Palakkad, to prototype testing, is described together with the planned hydrological, structural and control-design work. Expected benefits are quicker response, less routine manual intervention, better public-safety awareness and more efficient use of stored water. No experimental result is reported here; every performance claim is deferred to prototype testing and validation.***

Keywords: automatic dam gate, reservoir monitoring, water-level sensor, microcontroller, Internet of Things, flood warning, threshold control, spillway, prototype testing.

I. INTRODUCTION

Dams are among the most consequential structures in civil engineering. Besides storing water for irrigation and drinking supply, they generate hydroelectric power and hold back flood peaks. How well a dam performs these jobs depends largely on how its storage is managed and how water is let out through gates and spillways. In periods of heavy rainfall or sudden inflow the reservoir can climb quickly, so decisions about gate movement have to be made on time to keep levels in range and to limit risk to people and property downstream.

At many installations gates are still watched and operated by hand. Manual practice is vulnerable to slow communication, difficult site access and the burden placed on an operator who must read changing conditions and decide quickly. An automatic arrangement can ease this burden: it reads the reservoir level without a break, acts when a set limit is reached, and can pass the same information to remote observers through alerts and online dashboards.

The system studied here joins four ideas: water-level sensing, a controller, an automatic gate mechanism, and warning or monitoring facilities. Readings are processed by the controller and compared with preset levels, and the gate is then told to open, close or hold. Where network facilities exist, the level and any alert can be viewed remotely. It is important to say at the outset that this is a control and decision-support concept. Before it could be used on a real dam it would need detailed engineering design, safety checks, testing and dependable backup arrangements, and gate operation would still have to respect inflow, downstream conditions, the dam's own operating rules and public-safety requirements.

The main contributions of this paper are: (i) a structured account of the proposed monitoring-and-control concept and its components; (ii) a comparison of four published studies and the research gap they point to; (iii) a ten-stage methodology applied to a chosen site; and (iv) a plan of detailed design and testing work, with the performance measures to be recorded. The remaining sections follow this order.

II. RELATED WORK

Four studies were reviewed because each addresses a different layer of the same problem: prediction, threshold-based actuation, remote supervision and low-cost deployment.

©IJRASET: All Rights are Reserved

A. AI-Based Smart Dam Management

Dhavan and Kolhe [1] describe an intelligent management scheme aimed at dam safety and flood prevention. Field sensors report water level, rainfall, temperature and humidity, and the authors also mention seismic and structural data for wider monitoring. Readings travel wirelessly to a base station and are held on a cloud platform, so operators can look at current and past conditions from a distance. A stacked dense Long Short-Term Memory (LSTM) network, a deep-learning model suited to sequential data, is proposed to forecast water-level changes and flag conditions that could lead to overflow. Forecasts and preset thresholds then help suggest a release schedule; depending on the safety design, the gate may act automatically or wait for an operator's confirmation. A dashboard shows readings, predictions and recommendations, and SMS or e-mail alerts warn responsible staff. The authors also remind readers that maintenance, sedimentation, environmental effects and nearby communities matter as much as level control, and that such a model must be tested on historical and real-world data before it is trusted with safety-critical decisions.

B. Automatic Shutter Opening and Flood Detection

Jagtap et al. [2] built an automated system to watch dam levels and detect flood-like conditions with less human involvement. Their prototype pairs an ESP8266 microcontroller with an ultrasonic level sensor, a raindrop sensor, a flow sensor, a servo motor and the Blynk IoT application. The ultrasonic unit reads the reservoir level, the raindrop sensor detects rain, and the flow sensor tracks changes in water movement. When a programmed level is crossed, the controller drives the servo to release excess water. Through Blynk, users can follow level, rainfall, flow and gate status remotely and receive alerts when the level turns critical. Accuracy of the sensors, network reliability, continuous power and a sound gate mechanism are named as conditions for success, and the authors suggest machine-learning prediction, more environmental sensors, solar backup, SMS or voice alerts and cloud data logging as later improvements.

C. Smart Water Resource Management

Kulkarni et al. [3] begin from the observation that traditional management rests on manual observation and operator experience, which can slow decisions during heavy rain or sudden inflow. Earlier work they discuss uses ultrasonic or float-type sensors with microcontroller units, where preset thresholds trigger alarms or gate opening, and some systems add motor-driven gates to cut human intervention and operating errors. Others send data to remote stations over GSM, Wi-Fi or cloud services. The authors note that many IoT solutions raise complexity and cost, and they argue for a low-cost, reliable and locally deployable gate-control system built on embedded hardware, aimed at small and medium dams.

D. IoT-Based Dam Water Monitoring

Gaikwad and Badmera [4] propose an IoT-oriented system for monitoring levels and giving early warning. It uses an ESP8266 controller and an ultrasonic sensor, supported by a power supply, transformer, relay module, LEDs and a buzzer. Four level conditions, reported as 20, 40, 60 and 85, switch on corresponding LEDs and the buzzer; the paper does not state their units, so they are quoted here exactly as reported and are not converted. When a limit is crossed an alert can be sent and the shutter can open automatically.

Information is shared through cloud services and smartphones over local Wi-Fi, so people near the dam as well as operators can be warned without anyone being on site. The paper's own review mentions cloud-based flood detection, neural-network and neuro-fuzzy level prediction and model-predictive flood control, but these are background, not parts of the proposed design. The work has not been shown to be validated at full scale under severe weather.

E. Comparison and Research Gap

Table I sets the four studies side by side. All of them try to shorten the gap between a rising level and a response. They differ in where intelligence sits: in a prediction model [1], in a simple threshold program [2], [4], or in a low-cost embedded controller meant for smaller dams [3].

The reviewed material does not give enough information to rank the systems by accuracy, cost or field performance, so no such ranking is attempted here. What the literature does show is a need for a simple, affordable and testable workflow that combines sensing, threshold logic, staged gate action, local and remote warning, and defined behaviour under failure. This project aims to fill that space at prototype scale.

TABLE I
COMPARISON OF REVIEWED STUDIES

Ref.	Core approach	Main feature and stated caveat
[1]	Stacked LSTM prediction with cloud data	Forecasts level and suggests releases; needs testing on real data
[2]	ESP8266, ultrasonic, rain and flow sensors, servo, Blynk	Automatic shutter and remote alerts; needs field validation
[3]	Embedded threshold control for small and medium dams	Low-cost, local deployment; IoT adds cost and complexity
[4]	ESP8266, ultrasonic sensor, LEDs, buzzer, relay, Wi-Fi	Four-level warning and shutter opening; units not stated

III. PROPOSED SYSTEM

A. *System Concept*

The system works as a loop of sensing, deciding, acting and informing. Sensors measure the reservoir level and pass it to a controller. The controller checks the reading against predefined thresholds and, when one is reached, commands the gate mechanism. Monitoring and warning functions tell operators or nearby communities when specified conditions occur. Fig. 1 shows the arrangement, and the functions can be summarised as follows.

1) *Water-Level Monitoring:* Sensors measure the reservoir level on a continuous basis.
2) *Data Processing:* A microcontroller reads the sensor values and evaluates them against preset limits.
3) *Gate Actuation:* A motor or actuator moves the gate according to the control logic.
4) *Monitoring and Alerts:* An IoT platform or communication link can show live status and issue alerts.
5) *Safety and Verification:* Operating limits, manual override, power backup, handling of sensor failure and safe gate movement are settled during detailed design.




Fig. 1 Block diagram of the proposed automatic dam operating system

B. *Main Components*

1) *Water-Level Sensor:* It measures the reservoir level continuously and sends the data to the controller, which lets the system tell low, normal and critical levels apart. Ultrasonic sensors are the choice considered for the prototype.
2) *Microcontroller:* Acting as the brain of the system, it processes sensor data, compares the level with predefined limits and controls gate operation. The ESP8266 and Arduino-type boards are the candidates.

©IJRASET: All Rights are Reserved

3) *Motor:* It converts electrical energy into mechanical movement, opening or closing the gate on the controller's command and reducing the need for manual operation. Servo motors are planned for the scaled model.
4) *Dam Gate:* The gate governs release from the reservoir. It opens when a specified high level is reached and closes or reduces its opening as the level falls, always subject to the operating rules.
5) *Power Supply:* It feeds the sensors, controller and actuator, and a battery backup can carry the system through supply interruptions, which keeps operation dependable.
6) *Alarm and Warning Unit:* A buzzer, warning light or remote notification gives an alert when the level reaches a critical limit and warns operators about possible flooding or abnormal conditions.
7) *Communication Module:* An IoT, GSM or Wi-Fi module sends real-time level information to operators, enables remote monitoring and can deliver alerts to a mobile phone or monitoring station.

C. Objectives

The study sets out to: automate the opening and closing of gates according to predefined water-level conditions; monitor reservoir level continuously with sensors; support timely gate operation and help reduce flood risk; lower routine human intervention and operating errors; improve water management for irrigation, storage and controlled release; and enable real-time monitoring and alerts wherever communication technology is available.

D. Scope and Application Areas

The concept is relevant to flood control and disaster management, smart water-resource management, automation support at hydroelectric stations, regulation of irrigation water, remote monitoring and control, and integration with smart-city and smart-water infrastructure projects.

IV. METHODOLOGY

A. Overview

The work moves through ten stages, from the first study of a site to a tested demonstration model, as shown in Fig. 2. Each stage feeds the next, so an early choice such as the water-level range carries through to sensor placement, threshold selection and the test plan.




Fig. 2 Flow chart of the methodology

B. Stages of the Work

1) *Site Selection:* Kanjirampuzha Dam in Palakkad has been chosen as the study site because of its suitability and relevance to the objectives of the project.
2) *Site Study and Data Collection:* Information on reservoir level, inflow pattern, rainfall, gate arrangement, spillway characteristics and operating constraints is gathered where available. For the prototype, tank dimensions, sensor mounting position, water-level range and test conditions are defined.

©IJRASET: All Rights are Reserved | SJ Impact Factor 7.538 | ISRA Journal Impact Factor 7.894 |

3) *Reservoir and Hydrological Analysis:* The influence of inflow, storage and controlled outflow on reservoir level is studied, and the conditions that should raise alerts or gate commands are identified. Threshold values are chosen for this particular system and are not copied from another project.
4) *Structural Assessment of the Dam:* The structural arrangement and operating needs of the dam, or of a representative model, are reviewed with attention to gate movement, water pressure, supports and safe discharge. Any real-dam design or modification would need review by qualified dam and structural engineers.
5) *Spillway and Gate Design:* The roles of spillway and gate in regulating water are identified, and a gate mechanism and actuator suited to the model size and expected load are selected. The design should prevent jamming and uncontrolled movement and carry suitable physical limits.
6) *Water-Level Monitoring System:* A sensor, for example ultrasonic, is mounted where it gives consistent readings and is connected to the controller. Readings are checked at several known levels, and the sensor is protected against moisture, electrical faults and false readings.
7) *Automatic Gate Operating System:* The controller is programmed to compare readings with thresholds and to command the actuator to open, close or hold the gate. Hysteresis, or separate opening and closing thresholds, may be added so the gate does not keep switching when readings fluctuate.
8) *Flood Warning and Safety:* Warning conditions are defined, with local indicators and remote notifications where the prototype supports them. Communication failure, power loss, sensor failure, manual override and a safe default state are all considered. Alerts supplement established dam-safety procedures and do not replace them.
9) *Prototype Construction:* The tank or reservoir model, sensor, controller, actuator, gate, power supply and optional monitoring interface are assembled. Wiring, enclosure protection, gate travel and emergency stopping are checked before any water test.
10) *Performance Evaluation:* The system is tested at different water levels while sensor readings, threshold detection, gate operating time, actuator response and alert delivery are recorded. Tests are repeated for consistency, and failures are documented and corrected before conclusions are drawn.

V. PLANNED DESIGN AND ANALYSIS

The first phase fixed the concept and the site. The next phase turns the stages above into detailed work, outlined below.

A. *Site Data and Hydrological Analysis*

The chosen site will be studied for topography, stream course, catchment area, soil and rock conditions and the downstream area that a release would affect. Rainfall, inflow and past flood records are to be requested from the irrigation, water-resources or meteorological departments, and a site data table and contour map will be prepared, from which the prototype scale is fixed. Catchment runoff and peak flood discharge will be estimated with standard methods such as the rational method or the unit hydrograph. An elevation–storage capacity curve will be drawn, dead, normal and maximum water levels will be fixed, and from them the low, medium, high and danger thresholds that trigger gate operation and alerts will be defined.

B. *Spillway and Gate Design*

The spillway will be designed to pass the estimated design flood safely. The number, width and height of the gates will be decided, and the discharge through each gate and the hydrostatic force on it will be calculated. A suitable gate type, such as vertical lift or radial, will be selected, and the opening mechanism will be matched to the force and to the servo or motor capacity.

C. *Structural Check of the Dam Section*

The selected section will be checked for stability against overturning, sliding and uplift, with base pressures and factor of safety verified at normal and maximum reservoir levels. This confirms that the structure itself is sound before automatic operation is added to it.

D. *Control Logic and Fail-Safe Behaviour*

Gates open when the level crosses a threshold and close when it falls back. Servo motors are planned to open the gates in stages in proportion to the level instead of all at once. A manual override and a fail-safe response to sensor or power failure are included, together with a reliable supply and backup. Table II gives an illustrative alert ladder; the actual threshold values will come only from the hydrological analysis.

©IJRASET: All Rights are Reserved | SJ Impact Factor 7.538 | ISRA Journal Impact Factor 7.894 |

TABLE II
ILLUSTRATIVE ALERT LEVELS (VALUES TO BE FIXED)

Level	Intended system response
Low	Continuous monitoring and logging; gate stays closed
Medium	Status indication at the control panel; readings logged
High	Warning LED and buzzer; staged gate opening; remote alert
Danger	Danger LED and buzzer; further opening; SMS or IoT alert; downstream notification procedure

E. Monitoring and Warning

The level is shown on an LCD and a level indicator, and readings are logged for later analysis. The sensor is calibrated against a manual gauge to confirm accuracy. Status, warning and danger LEDs and a buzzer show the alert level at the control panel, while IoT alerts through a platform such as Blynk, or by SMS or e-mail, allow remote monitoring and early warning. A simple procedure for informing downstream areas at each alert level will be defined.

F. Prototype

A scaled model will be built with a reservoir tank, dam body, spillway, gates and downstream channel. The sensor, microcontroller, servo motors, display and alarm will be integrated and waterproofed where needed, and a pump or inlet will simulate inflow so that rising levels can be tested.

G. Performance Evaluation

The prototype will be run under different inflow rates, and automatic operation will be compared with manual operation. Table III lists the measures to be recorded, in line with the summary of the literature. Results, limitations and suggestions for improvement will be documented in the final report.

TABLE III
PERFORMANCE MEASURES FOR PROTOTYPE TESTING

Measure	What is recorded
Reading consistency	Repeated sensor readings at known levels against a manual gauge
Response time	Delay between crossing a threshold and gate movement
Actuator operation	Whether the gate opens, closes and holds correctly
Alert delivery	Timing and success of local and remote alerts
Failure behaviour	System response to sensor, communication or power failure
Automatic vs. manual	Comparison across different inflow rates

VI. EXPECTED BENEFITS AND LIMITATIONS

If the prototype performs as intended, the approach should allow faster response during heavy rainfall, less dependence on manual operation, better public-safety awareness through timely alerts and more efficient use of water resources. These benefits are expectations drawn from the concept and from the literature; they are not measured results. They depend on suitable sensor selection, reliable control logic, correct gate and actuator design, dependable communication and power, and well-defined safety procedures.

Several limitations must be kept in view. Sensor accuracy can be affected by moisture, electrical faults and false readings. IoT links raise cost and complexity and fail when the network does. Prediction models need real-world data before they can support safety-critical decisions. A prototype cannot represent every condition of a full-scale dam, so use on an actual dam would call for detailed engineering review, compliance with applicable regulations and integration with the operator's safety procedures.

VII. CONCLUSION

This paper has described an Automatic Dam Operating System that couples continuous level sensing with threshold-based gate control, warnings and remote monitoring. A review of four studies showed shared aims but different emphasis, and left room for a simple, affordable and thoroughly tested workflow. A ten-stage methodology for Kanjirampuzha Dam, Palakkad, and a plan covering hydrology, gate design, structural checks, control logic, alerts, prototype construction and evaluation were set out. The next phase will concentrate on building the prototype, calibration, repeated performance testing, fault handling and evaluation against the stated objectives. Only then can the benefits discussed here be confirmed or corrected.


VIII. ACKNOWLEDGMENT

The authors thank the project guide and coordinator, Ms. Anagha, Assistant Professor, and the Head of the Department of Civil Engineering, Ms. Fathima Fayiza Elachola, for their interest and encouragement, together with the management of Eranad Knowledge City Technical Campus, the department staff and their families and friends.

REFERENCES

[1] A. H. Dhavan and P. S. Kolhe, "AI-driven smart dam management system for enhanced safety and flood prevention," J. Adv. Future Res. (JAAFR), vol. 4, no. 6, 2026.
[2] D. S. Jagtap, R. R. Tamnur, S. M. Shaikh, and S. V. Aursang, "Automatic dam shutter opening and flood detection system," J. Emerg. Technol. Innov. Res. (JETIR), vol. 12, no. 4, Apr. 2025.
[3] M. M. Kulkarni, V. G. Bharti, N. S. Narute, S. V. Bangar, and S. R. Hingane, "Smart water resource management of dam," Int. J. Sci. Res. Eng. Dev. (IJSRED), vol. 9, no. 1, 2026.
[4] P. Gaikwad and M. S. Badmera, "Dam water monitoring system using IoT," Int. Res. J. Eng. Technol. (IRJET), vol. 9, no. 6, Jun. 2022.

©IJRASET: All Rights are Reserved | SJ Impact Factor 7.538 | ISRA Journal Impact Factor 7.894 |



10.22214/IJRASET

45.98

IMPACT FACTOR: 7.129

IMPACT FACTOR: 7.429

INTERNATIONAL JOURNAL FOR RESEARCH

IN APPLIED SCIENCE & ENGINEERING TECHNOLOGY

Call : 08813907089 (24*7 Support on Whatsapp)