iJRASET
International Journal For Research in Applied Science and Engineering Technology



INTERNATIONAL JOURNAL FOR RESEARCH

IN APPLIED SCIENCE & ENGINEERING TECHNOLOGY

Volume: 6 **Issue:** I **Month of publication:** January 2018

DOI: http://doi.org/10.22214/ijraset.2018.1097

www.ijraset.com

Call: 08813907089 | E-mail ID: ijraset@gmail.com

International Journal for Research in Applied Science & Engineering Technology (IJRASET)
ISSN: 2321-9653; IC Value: 45.98; SJ Impact Factor :6.887
Volume 6 Issue I, January 2018- Available at www.ijraset.com

Computational Investigation of Flow Stability of Baffled Pipe

Bhojram Dhanker[1], Dr. D. N. Dewangan[2]
[1, 2]*Department of Mech. Engg, Rungta College of Engg. And Tech., Raipur, C. G., India*

Abstract: ***In this paper, comparative flow stability within the straight pipe and the baffled pipe has been investigated using computational fluid dynamics (CFD). The k-ε turbulence model has been used to simulate high turbulent flow within the pipe. The flow stability has been analyzed in terms of skin friction coefficient and wall shear stress for a wide range of Reynolds number. The effect of baffle orientation has also been seen. It has been found that on increasing baffle orientation angle, the flow gets reversed at low Reynolds number and the flow is quite unstable.***
Keywords: Computational fluid dynamics, Baffles, Stability, CFD, Reynolds Number

I. INTRODUCTION

Baffles are the important structural element of shell and tube type heat exchanger, which acts as an obstruction and/or flow-directing panel or vanes employed in some industrial process ducts, vessels and pipes, mostly in case of tube and shell heat exchangers, static mixers and chemical reactors to take the advantage of mixing, momentum transfer and formation of secondary flow. It is generally used in various engineering applications. Baffles are designed to direct the flow of fluids in order to maximize the thermal efficiency and to support tube bundles.

There are three basic modes of heat transfer; Conduction, Convection, and Radiation. Conduction is practically involved in all operations in which heat interaction taking place. Baffles are the commonly used structural element, which is applied in transmitting heat by the mode of conduction especially in channels and ducts in process industries.

II. LITERATURE REVIEW

Howe's et al. (1991) has been numerically simulated the natural and forced unsteadiness of flow in the baffled pipe for the periodic flow and illustrated the chaotic advection, the mixing mechanism and fouling rates of the flow. Gaddis and Gnilinski (1997) using the novel method to calculate the pressure drop within shell and tube heat exchanger in presence of baffles; based on correlations. The obtained results have been compared with experimental work and get ± 35% variations. Sun and Emery (1997) applied finite volume method to solve the governing equations and investigated the convective heat transfer of a two-dimensional enclosure filled with air along with having internal baffles, which acts as internal heat sources. The obtained experimental and numerical result using window calorimeter is compared in terms of temperature distribution. Kang and Yang (2012) examined the flow instability of channel with the baffle in three-dimensional flows. They have been observed the influence of aspect ratio of baffles, baffle spacing, and baffle height for the given range of Reynolds number.

Salahudd in et al. (2015) presented a comprehensive comparative report on the performance of helical and segmental baffles in shell and tube heat exchanger and found that helical baffles have superior performance as compared to helical baffles. A novel approach has been represented by Mehdi et al. (2015) for improving the energy efficiency of shell and tube heat exchanger using helical baffles with nano-fluid. The influences of overlapping and decrease in helix angle of baffles have been examined and found that pressure drop and heat transfer increases as the concentration of nano fluid increases. The results have been optimized by single-objective optimization using Neural Network.

Bin et al. (2015) experimentally examined the performance of baffle helix angle along with discontinuous helical baffles in shell tube heat exchanger. The analysis based on the second law of thermodynamics represents, the superior performance in terms of heat transfer for smaller helix angle. The effect of the baffle on flow distribution of an electrostatic precipitator has been presented by Sayema et al. (2015) for the coal based power plant. The result shows that residence time of flue gas in electrostatic precipitator increases, which ultimately increases the collection efficiency and effective mixing of particles.

Cong et al. (2017) studied the thermal performance of trisection helical baffles heat exchangers with diverse inclination angles and baffle structures. They represented that the sector baffles have better performance as compared to ellipse baffles and concluded that overlapping of baffles is not beneficial.

©IJRASET (UGC Approved Journal): All Rights are Reserved

III. MATHEMATICAL MODELING

Navier-stokes equation has been used for fluid flow in baffled channel, duct, pipe etc. and governed by the Bernoulli's equation of flow (Yadav et al., 2017). For analyzing the fluid flow across the pipe Navier–Stokes equations are solved by using ANSYS Fluent solver. The details of equations are as follows:

$$\rho\frac{Du}{Dt} = -\frac{\partial p}{\partial x} + div(\mu gradu) + S_{Mx} \quad \text{..... (1)}$$

$$\rho\frac{Dv}{Dt} = -\frac{\partial p}{\partial y} + div(\mu gradv) + S_{My} \quad \text{..... (2)}$$

$$\rho\frac{Dw}{Dt} = -\frac{\partial p}{\partial z} + div(\mu gradw) + S_{Mz} \quad \text{..... (3)}$$

Governing equations of the flow of a compressible Newtonian fluid

Continuity $\frac{\partial \rho}{\partial x} + div(\rho u) = 0$ ..... (4)

x-momentum $\frac{\partial(\rho u)}{\partial x} + div(\rho uu) = -\frac{\partial p}{\partial x} + div(\mu gradu) + S_{Mx}$ .....(5)

y-momentum $\frac{\partial(\rho v)}{\partial y} + div(\rho vu) = -\frac{\partial p}{\partial y} + div(\mu gradv) + S_{My}$ ..... (6)

z-momentum $\frac{\partial(\rho w)}{\partial z} + div(\rho wu) = -\frac{\partial p}{\partial z} + div(\mu gradw) + S_{Mz}$ ..... (7)

Energy $\frac{\partial(\rho i)}{\partial t} + div(\rho iu) = -pdivu + div(kgradT) + \Phi + S_i$ ..... (8)

Using various correlation FEV results are been compared analytically

$$h_f = f\frac{LV^2}{D_h 2g} \quad \text{..... (9)}$$

$$f = \frac{64}{\text{Re}} \text{ (For Re<2000)} \quad \text{..... (10)}$$

$$\text{Re} = \frac{\rho u_{avg} d}{\mu} \quad \text{..... (11)}$$

Where, f is the friction factor for fully developed laminar flow; L is the length of the pipe; V is the mean velocity of the flow; d is diameter of the pipe and Re is the Reynold Number

IV. METHODOLOGY

In this work CAD model of Baffled pipe have been developed and the orientation of baffles have been varied at a different angle. The CAD model of baffled pipe has been discretized in a different number of nodes and element which is in order of 10^6. The Geometrical details of baffled pipe are shown in figure 1.

©IJRASET (UGC Approved Journal): All Rights are Reserved

ISSN: 2321-9653; IC Value: 45.98; SJ Impact Factor :6.887
Volume 6 Issue I, January 2018- Available at www.ijraset.com




Figure 1: Geometrical details

V. RESULT AND DISCUSSIONS

To study the flow instability within the baffled pipe at different baffle arrangement; the velocity distribution, turbulent intensity, and the pressure distribution have investigated in detail along the channel length. Figure 2 shows the comparison of turbulent intensity along the pipe length. It has been shown that when the fluid flows in a straight pipe, the turbulent intensity increases linearly but when the fluid flows in the baffled section, the turbulent intensity is increased at a higher rate. This trend has been shown that the baffled pipes gives effective turbulence and increase of heat transfer in pipe flow.

©IJRASET (UGC Approved Journal): All Rights are Reserved




Figure 2: Comparison contour plot of turbulent intensity along the pipe length

©IJRASET (UGC Approved Journal): All Rights are Reserved




Figure 3: Comparison of pressure distributions along the pipe length

Figure 3 shows the comparison of pressure distribution along the pipe length. It has been shown that when the fluid flows, the flow is stable till it reaches the baffled section. After reaching baffled section, the flow becomes unstable due to mass and momentum

©IJRASET (UGC Approved Journal): All Rights are Reserved

transfer and the pressure reduces in a zigzag manner. The same trend has been seen for the entire baffle oriented pipe but the rate of pressure decreases. It has also been seen that the drop in pressure increase as the baffle orientation increases.




Figure 4: Comparison of turbulent intensity along the pipe length

Figure 4 shows the comparison of turbulent intensity along the pipe length. It has been seen that when the fluid flows, at the baffled section the turbulent intensity increase rapidly. After passing through the baffled section there is a drop in turbulent intensity. The same trend has been seen for the entire baffle oriented pipe but the rate of turbulence changes. Therefore, in heat exchanger cases

©IJRASET (UGC Approved Journal): All Rights are Reserved

numbers of the baffle are increased so that the turbulent intensity can be increased significantly which will increase the heat transfer rate.




Figure 5: Comparison of velocity distribution along the pipe length

©IJRASET (UGC Approved Journal): All Rights are Reserved

Figure 5 shows the comparison of velocity distribution along the pipe length. It has been seen that when the fluid flows; the flow is stable till it reaches the baffled section. After reaching baffled section, the flow becomes unstable and the velocity increases because of mass and momentum transfer. The same trend has been seen for the entire baffle oriented pipe but the rate of velocity changes.

VI. CONCLUSIONS

In this work, the flow stability has been examined for fully developed turbulent flow and following conclusions have been drawn:

A. At high Reynolds number due to the presence of baffles, the flow gets unstable which ultimately affect the various parameters such as pressure, velocity, and turbulent intensity.
B. As the baffle orientation varies the parameters such as pressure, velocity, and turbulent intensity varies significantly.
C. The velocity increase within the pipe as it passes over the baffles.
D. The turbulent intensity increase within the pipe as it passes over the baffles.

REFERENCES

[1] Bin Gao, QinchengBi,ZesenNie, and Jiangbo Wu, "Experimental study of effects of baffle helix angle on shell-side performance of shell-and-tube heat exchangers with discontinuous helical baffles", Experimental Thermal and Fluid Science, Volume 68, Pages 48–57, 2015.

[2] Budzaki S. and Seruga B., "Determination of convective heat transfer coefficient during frying of potato dough", Journal of Food Eng. Volume 66, Issue 3, Pages 307–314, 2005.

[3] Cong Dong, Xin-Fa Zhou, Rui Dong, You-QuZheng, and Wen-Wen Guo, "An analysis of performance on trisection helical baffles heat exchangers with diverse inclination angles and baffle structures", Chemical Engineering Research and Design, Volume 121, Pages 421-430, May 2017.

[4] Dhanker B. R. and Dewangan D. N., Investigation of Flow Stability of Baffled Pipe – A Comprehensive Report", International Journal of InnovativeRresearchin Science, Engineering, and Technology, Volume 6, Issue 7, Pages 12680-12685, July 2017.

[5] Edward S. Gaddis and Volker Gnielinski, "Pressure drop on the shell side of shell-and-tube heat exchangers with segmental baffles", Chemical Engineering and Processing: Process Intensification, Volume 36, Issue 2, Pages 149-159, April 1997.

[6] Howes T., MackleyM.R., and Roberts E.P.L., "The simulation of chaotic mixing and dispersion for periodic flows in baffled channels", Chemical Engineering Science, Volume 46, Issue 7, Pages 1669-1677, 1991.

[7] Ito S., et al., "Conceptual design and cooling blade development of 1700 C-class high-temperature gas turbine", ASME Turbo Expo 2003, collocated with the 2003 International Joint Power Generation Conference, American Society of Mechanical Engineers, 2003.

[8] Kang Changwoo and Yang Kyung-Soo, "Flow instability in baffled channel flow", International Journal of Heat and Fluid Flow, Volume 38, Pages 40-49, Dec. 2012.


[9] Mehdi Bahiraei, MortezaHangi, and Mahdi Saeedan, "A novel application for energy efficiency improvement using nanofluid in shell and tube heat exchanger equipped with helical baffles", Energy, Volume 93, Part 2, Pages 2229-2240, Dec. 2015.

[10] Salahuddin U., Bilal M., and EjazHaider, "A review of the advancements made in helical baffles used in shell and tube heat exchangers", International Communications in Heat and Mass Transfer, Volume 67, Pages 104-108, Oct. 2015.

[11] Sayema A.S.M., Khana M.M.K., Amanullah M.T.O., Rasula M.G., and Hassan N.M.S., "Effects of Baffles on Flow Distribution in an Electrostatic Precipitator (ESP) of a Coal Based Power Plant", Procedia Engineering, Volume 105, Pages 529-536, 2015.

[12] Sun Y.S., and Emery A.F., "Effects of wall conduction, internal heat sources and an internal baffle on natural convection heat transfer in a rectangular enclosure", International Journal of Heat and Mass Transfer, Volume 40, Issue 4, Pages 915-929, March 1997.

©IJRASET (UGC Approved Journal): All Rights are Reserved



10.22214/IJRASET

45.98

IMPACT FACTOR: 7.129

IMPACT FACTOR: 7.429

INTERNATIONAL JOURNAL FOR RESEARCH

IN APPLIED SCIENCE & ENGINEERING TECHNOLOGY

Call : 08813907089 (24*7 Support on Whatsapp)